

	OCP Ready v1 Data Center Site Assessment	GLOBAL SWITCH AMSTERDAM EAST		
	Self Assessment Status:	COMPLETE-MEETS REQUIREMENTS		
	Data Center Location Name	AMSTERDAM EAST - STAGE 1		
	Data Center Location Address	Johann Huisingalaan 759, 1066VH AMSTERDAM		
	Site Development Category:	1. Data Center Fully Leased	01/01/2026	
	Site Description: IT Technical Space (White Space) Area	Technical Suites A01, A02, B01, B02		
	Site Description: Critical IT Power	2000kW per Suite (8MW Total for Stage 1) supported from Static UPS and standby generation. Cooling to be delivered from chiller assist cooling and fan walls to achieve an annualised PUE <1.2. Facility to be constructed over five stages to give 32MW IT.		
	Site Description: Network Provider Availability	Global Switch Amsterdam is one of the most connected hubs in the country and currently hosts a multitude of global and national telecommunications and cloud providers, AMS-IX and NL-IX, as well as a wide range of internet services providers. With diverse fibre connectivity on the campus, customers of Amsterdam East will be able to access this connectivity rich environment and benefit from a wide choice of cloud and network providers as well as direct access to the global IP backbone		
	Site Description: Facility Features	New Build Data Centre, power density ~ 3000W/m2, annualised PUE < 1.2. Communal heat export. Technical suites supported from Static UPS and standby generation. Cooling to be delivered from chiller assist cooling and fan walls.		
	Site Description: Other Services	The new building will sit on the existing campus adjoining Amsterdam West		
	Date Original Assessment is Completed	07/29/2020		
	Re-Assessment Date:			
Ref:	REQUIREMENTS - Attribute (Must have an Optimum or Acceptable result)	Parameter	Result	Notes/ Actual Parameters
1.0	ACCESS			
1.0-A	Building Access	1. Loading dock with lift or leveler	Optimum	External Loading bay is provided with two scissor lift devices to offload crated racks from the delivery vehicle truck into the unloading area. The crates can then be transported 'threshold free' into the uncrating space.
1.0-B	Delivery pathway, Loading dock to Goods in	1. ≥2.75m (108in) H x ≥2.4m (96in) W x ≥2.4m (96in) D unobstructed access and threshold free	Optimum	Access through the loading area to the uncrating area is designed for the wooden crate to be transported on a pallet truck; the loading bay door has a clear dimension of 2.4m wide x 3m high.
1.0-C	Delivery pathway, Goods in to White space	1. ≥2.4m (96in) H x ≥1.8m (72in) W unobstructed access and threshold free	Optimum	Access from the uncrating area to the technical suites (data halls) is 'threshold free' so the rack can be transported fully populated on its casters into the suites, all access door are sized for 3m high and 1.8
1.0-D	Corridor floor rolling load	1. ≥680kg (1500lb) (6.67kN)	Optimum	The floor throughout the new building comprises in-situ cast composite concrete floor slab. Floor provides smooth movement of 1,500kg rack on four caster wheels and is designed for a uniform load of 15kN/m2.
1.0-E	Unboxing/pre-staging/storage area floor uniform load	1. ≥1221kg/m2 (250lb/ft2) (11.97kN/m2)	Optimum	Raised floor in the uncrating area - 12.0kN/m²
1.0-F	Unboxing/pre-staging/storage area floor concentrated load	2. ≥459kg (1012lb) (4.5kN) (Notes Required)	Acceptable	Point load for raised floor (25mm x 25mm) is 4.5kN. 4 -point load 25 x 25mm = 11kN; however four wheels of a 600mm x 1000mm rack will not fall onto a 600mm x 600mm floor tile. Floor tiles are tested in accordance with PSA MOB PF2 PS/SPU for raised access floors. All working loads perform to a 3x safety factor and to a safety factor of 2 for 11kN load.
1.1	RAMPS			
1.1-A	Gradient	1. Not Applicable - No Ramps Required	Optimum	No ramps installed within the facility
1.1-B	Width	1. Not Applicable - No Ramps Required	Optimum	No ramps installed within the facility
1.1-C	Landing area	1. Not Applicable - No Ramps Required	Optimum	No ramps installed within the facility
1.1-D	Railings	1. Not Applicable - No Railings Required	Optimum	No ramps installed within the facility
1.2	LIFTS / ELEVATORS			
1.2-A	Weight loading	1. ≥1500kg (3300lbs)	Optimum	A 4000kg Goods Lift is provided in the loading bay with a speed of 0.5 m/s
1.2-B	Door height	1. ≥2.4m (96in) Lift /Elevator door opening height (not internal cabin)	Optimum	Industrial type goods lift with 2500mm clear door opening height and 2600mm car internal clear height
1.2-C	Width	1. ≥1.5m (60in) Unobstructed door opening width	Optimum	1800mm wide unobstructed door opening
1.2-D	Depth	1. ≥1.5m (60in) Unobstructed cabin depth	Optimum	Lift car cabin - 2100mm (width) x 3400mm (deep) x 2600mm (height internal)
2.0	IT TECHNICAL SPACE (WHITE SPACE)			
2.0-A	Floor rolling load	1. ≥680kg (1500lb) (6.67kN)	Optimum	Technical Suites (data halls) floors comprise in-situ cast composite concrete floor slab. Floor provides smooth movement of 1,500kg rack on four caster wheels.
2.0-B	Floor uniform load	1. ≥1221kg/m2 (250lb/ft2) (11.97kN/m2)	Optimum	15.0kN/m² (1500 kg/m²)
2.0-C	Floor concentrated load	1. ≥680kg (1500lb) (6.67kN)	Optimum	In-situ cast composite concrete floor slab with a concentrated limit of 20kN (25mm x 25mm).
2.0-D	Finished floor to ceiling height	2. ≥3.1m (124in)	Acceptable	3900 mm clear height from top level of finished floor slab to the underside of the suspended ceiling.
2.0-E	Access floor clearance	1. Not Applicable - No Access Floor	Optimum	Basis of Design is no raised floor. If a raised floor is required by the Customer, it can be accommodated, but a ramp may be needed to access the Customer Whitespace.
2.1	ELECTRICAL			
2.1-A	Number of independent circuits to the rack	1. 2N (A+B)	Optimum	N+N power distribution to the rack from a Distributed Redundant UPS topology.

2.1-B	Maximum circuit capacity	1. 3ø 32A/230V	Optimum	Single and three phase tap off boxes can be provided, fed from an N+N overhead busbar solution. The rating of the tap-off boxes will be customer determined with multiple 16A or 32A outlets.
2.1-C	Circuit voltage	1. 400/230 VAC nominal	Optimum	Nominal 230v a.c. Single phase, 400 V a.c. 3 phase.
2.1-D	Circuit frequency	1. 47-63 Hz	Optimum	Nominal 50Hz, +/- 0.1 Hz
2.1-E	Power receptacle / WIP Type	1. IEC60309 460R9W	Optimum	Customer preference can be accommodated
2.1-F	Circuit receptacle location	1. Overhead	Optimum	Overhead via busbar. Busbar can be customer supplied or vendor nominated
2.1-G	Upstream UPS options	1. UPS and non UPS feeds available	Optimum	Basis of design is UPS backed IT power supply via centralised UPS with battery back up; however if the customer requires non UPS backed supplies this can be discussed.
2.1-H	Rack-based batteries permitted	1. Allowed	Optimum	Local battery storage in the IT racks is permitted but their use needs to be declared for the purposes of insurance.
2.1-I	Generator load acceptance time	1. <60 seconds	Optimum	Generator Load Acceptance Time is 35 - 45 seconds
2.2	COOLING			
2.2-A	Rack airflow direction	1. Front to Back	Optimum	Front to back - flooded room cooling with hot aisle cooling
2.2-B	Air containment methods	1. Hot aisle containment or rack chimney	Optimum	Hot aisle containment is the basis of the system design.
2.2-C	Maximum rack density	1. ≥12kw	Optimum	> 12kW. Flooded room cooling so lesser constraints on rack load
2.2-D	Minimum cold aisle width	1. ≥1500mm (60in)	Optimum	A cold aisle width of 1500mm is achievable and this could be reduced to 1200mm to achieve a higher count.
2.2-E	Minimum free width cold aisle (Inside cage)	1. ≥1200mm (48in)	Optimum	1200mm can be provided
2.2-F	Minimum hot aisle width	1. ≥1200mm (48in)	Optimum	Hot aisle containment is the basis of design and the standard pitch is 1200mm to tie up with the structural ceiling penetration.
2.2-G	Inlet air conditions	1. ASHRAE Class A1 Allowable	Optimum	The basis of design is ASHRAE Recommended range which is more stringent in terms of inlet temperature. However, controlled excursions into the allowable range A1 would be welcomed if accepted by the customer, so as to improve energy efficiency and total cost of operation to the customer. Humidity will also meet the recommended or allowable range.
2.2-H	Air quality	1. EN 779 G4 and F7 filtering & Gas particulate monitoring to the ANSI/ISA 74.04-1985 G severity levels	Optimum	Fresh air make-up AHUs are provided on an N+1 redundancy basis to maintain pressure control and humidity. Basis of design for AHU filtering is G4 and F7 as standard. Additional filtration will also be provided in the fan wall unit on the return air path. Where corrosion above Level G1 is detected, additional gaseous and particulate filtering can be provided.
2.2-I	Temperature rise	1. ≥12 Deg C DeltaT	Optimum	The basis of design is 12K (12°C pick up of heat from the inlet to the outlet of the IT equipment) across the IT rack, although high temperatures are permissible.
2.2-J	Cabinet blanking of open space	1. Mandatory	Optimum	Mandatory that customers provide blanking plates within their racks or where racks are not provided within a contained aisle.
2.3	CABLING			
2.3-A	Cabling infrastructure pathways	1. Top and Front of rack fed	Optimum	Top entry and front presentation for all power and network connectivity.
2.3-B	Overhead Network Infrastructure containment levels	1. 3 Levels (Intra-Pod cabling; Inter-Pod cabling; OOB cabling)	Optimum	The clear height of the technical space is 3900mm, which should accommodate 3 levels cabling; this is subject to customer requirements
2.3-C	Fibre Type (if installed)	2. Installed Per Customer Requirements	Acceptable	Dependent on Customer requirements
2.3-D	Fibre connection presentation (if installed)	2. Installed Per Customer Requirements	Acceptable	Dependent on Customer requirements
	CONSIDERATIONS (For information only)	Parameter	Result	Notes
3.0	SERVICE			
3.0-A	Replacement PSU Modules	2. Other (Notes required)	Acceptable	This service is not currently provided and would be dependant upon the ownership of the racks. However, a remote hands service could be agreed.
3.0-B	Replacement BBU Modules	2. Other (Notes required)	Acceptable	This service is not currently provided and would be dependant upon the ownership of the racks. However, a remote hands service could be agreed.
3.0-C	Option to monitor PSUs and BBUs	2. No	Acceptable	This service is not currently provided and would be dependant upon the ownership of the racks. However, a remote hands service could be agreed.
3.0-D	Remote hands for PSU and BBU replacement or expansion	2. No	Acceptable	This service is not currently provided and would be dependant upon the ownership of the racks. However, a remote hands service could be agreed.
3.0-E	Remote hands for OCP IT hardware replacement or expansion	2. No	Acceptable	This service is not currently provided and would be dependant upon the ownership of the racks. However, a remote hands service could be agreed.
4.0	EFFICIENCY			
4.0-A	Site Operations Standards	2. Other (Notes required)	Acceptable	Global Switch follow internal operational standards and have a Critical Environments Programme in place

4.0-B	Site PUE Monitoring	1. Continuously monitored	Optimum	The Technical Suite PUE will be continuously monitored using MID power meters at the supply to the overhead busbar (L2) which is reported back to the on-site PMS system. Additional more granular monitoring can be provided at the tap off to the IT racks.
4.0-C	Site Design PUE	1. <1.2	Optimum	The annualised PUE associated with the suite, including the shared infrastructure, will be less than 1.2 @ 100% IT load. An independent design PUE report is available upon request.
4.0-D	Site Annualized PUE Current Achievement	1. <1.2	Optimum	The predicted annualised PUE is <1.2 but the facility has not been operational for 12 months with customer load, therefore this metric score will be updated at that point
4.0-E	Site WUE Monitoring	1. Continuously monitored	Optimum	WUE will be monitored via water meters that supply the facility and sub-meters at the external cooling units that will use water to provide cooling. This consumption data will be continuously monitored by the on-site PMS system to generate a WUE value.
4.0-F	Site CUE Monitoring	1. Continuously monitored	Optimum	The on-site PMS will convert the energy consumption data to provide a continuous CUE metric.
5.0	OPENNESS			
5.0-A	PUE Published	2. Available upon request	Acceptable	The PUE related to the customers demise can be published to the customer.
5.0-B	Facility Design Drawings & Files	2. Available to view upon request	Acceptable	As Built drawings are available for customers and prospective customers to view. Online access to drawings that relate to a customers demise may, with prior consent, be accessible from the online Global Switch Customer portal.
	Site Assessment Version - v1.0 rev1.4			